

Alabama Department of Transportation
Proposal Item Summary

062. STPAA-0177(502)

CLARKE COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-177 from the junction of SR-13 (US-43) to the junction of Miller Street (MP 2.188) in Jackson. Length 2.177 mi.

The Bracket Estimate on this project is from \$1,177,312 to \$1,438,937.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C002	412	SQYD	Removing Concrete Slope Paving
206D002	548	LF	Removing Curb
212A000	159	STA	Machine Grading Shoulders
405A000	10,226	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	98,413	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing Certified Inertial Profiler
424A360	6,230	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	180	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	713	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	385	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	3	Mile	Scoring Bituminous Pavement Surface
430B043	50	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
614A000	248	CUYD	Slope Paving
623B000	133	LF	Concrete Curb, Type N
623B001	68	LF	Concrete Curb, Type N Special
650A000	50	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	8	Acre	Mowing
656A010	3	Acre	Mulching
665B001	1	Ton	Temporary Mulching
665G000	300	Each	Sand Bags
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 62,500.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	2,500	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	872	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701C001	17	Mile	Solid Temporary Traffic Stripe
703A002	10,271	SQFT	Traffic Control Markings, Class 2, Type A
703B002	368	SQFT	Traffic Control Legends, Class 2, Type A
703D002	2,700	SQFT	Temporary Traffic Control Markings (Paint)
703E002	112	SQFT	Temporary Traffic Control Legends (Paint)
705A030	81	Each	Pavement Markers, Class A-H, Type 2-C
705A031	239	Each	Pavement Markers, Class A-H, Type 1-A
705A032	388	Each	Pavement Markers, Class A-H, Type 1-B
705A037	305	Each	Pavement Markers, Class A-H, Type 2-D
705A038	194	Each	Pavement Markers, Class A-H, Type 2-E
740B000	828	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	400	Each	Cones (36 Inches High)
740I002	4	Each	Warning Lights, Type B
740M001	400	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit