

**Alabama Department of Transportation  
Proposal Item Summary**

---

**070. STPAA-STPOA-4214(258)**

**LIMESTONE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic Stripe on East Limestone Road from the junction of SR-2 (US-72) east of Athens to the intersection of Copeland Road. Length 4.858 mi.

The Bracket Estimate on this project is from \$718,343 to \$877,975.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
401B100	63,700	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	1,910	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A360	5,500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	2,900	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	166	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,000.00)
701A030	11	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	6	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	3	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
703A002	1,827	SQFT	Traffic Control Markings, Class 2, Type A
703B002	304	SQFT	Traffic Control Legends, Class 2, Type A
703D001	954	SQFT	Temporary Traffic Control Markings
703E001	136	SQFT	Temporary Traffic Control Legends
705A032	75	Each	Pavement Markers, Class A-H, Type 1-B
705A037	400	Each	Pavement Markers, Class A-H, Type 2-D
740B000	630	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car