

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**082. STPNU-5214(253)**

**MORGAN COUNTY**

Contract Time: 35 Working Days

DBE Goal Percent: 10.00

for constructing the Resurfacing, Guardrail Installation, and Traffic Stripe on CR-73 (Eva Road) from the junction of Peck Mountain Road to the intersection of SR-67 in Florette. Length 2.276 mi.

The Bracket Estimate on this project is from \$636,939 to \$778,481.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	50 LF		Removing Guardrail
206E019	4 Each		Removing Guardrail End Anchor (Type 10)
401B100	23,843 SQYD		Bituminous Treatment E (With Polymer Additive)
405A000	716 Gal		Tack Coat
407B000	4 Mile		Joint Sealant For Hot Mix Asphalt Pavement
408A051	13,534 SQYD		Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
410H000	1 Each		Material Remixing Device
420A015	609 Ton		Polymer Modified Open Graded Friction Course
420B000	2,436 Gal		Open Graded Friction Course Tack Coat
424A340	3,129 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	297 Ton		Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	2 Mile		Scoring Bituminous Pavement Surface
430B043	427 Ton		Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS		Mobilization
630A001	2,200 LF		Steel Beam Guardrail, Class A, Type 2
630C050	6 Each		Guardrail End Anchor, Type 20 Series
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 33,900.00).
701A231	5 Mile		Solid White, Class 2, Type A Traffic Stripe
701A235	5 Mile		Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1 Mile		Broken Yellow, Class 2, Type A Traffic Stripe
701B206	955 LF		Dotted, Class 2, Type B Traffic Stripe
701C000	2 Mile		Broken Temporary Traffic Stripe
701C001	12 Mile		Solid Temporary Traffic Stripe
703A002	1,022 SQFT		Traffic Control Markings, Class 2, Type A
703B002	68 SQFT		Traffic Control Legends, Class 2, Type A
705A032	38 Each		Pavement Markers, Class A-H, Type 1-B
705A037	556 Each		Pavement Markers, Class A-H, Type 2-D
740B000	293 SQFT		Construction Signs
740E000	50 Each		Cones (36 Inches High)
740M001	50 Each		Ballast For Cone
740O000	1 Each		Pilot Car