

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**085. STPAA-NR13(953)**  
**SUMTER COUNTY**

Contract Time: 35 Working Days

for constructing the Curb Ramp Installations and Modifications on various routes at various locations in Livingston and York as indicated by the plans.

The Bracket Estimate on this project is from \$114,469 to \$139,907.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	186	SQYD	Removing Concrete Sidewalk
206D002	162	LF	Removing Curb
305B077	25	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
408A054	100	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
539A004	36	LF	12 Inch Trench Drain
600A000	1	LS	Mobilization
618A000	191	SQYD	Concrete Sidewalk, 4" Thick
618C000	164	SQFT	Truncated Dome Retrofit
654A001	107	SQYD	Solid Sodding (Bermuda)
665E000	100	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665J002	200	LF	Silt Fence
665O001	200	LF	Silt Fence Removal
665Q002	200	LF	Wattle
674A000	500	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
703A002	5,726	SQFT	Traffic Control Markings, Class 2, Type A
703C001	810	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
740B000	1,052	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone