

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**093. STPOA-STPNU-4415(251)**

**MACON COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-69 from the junction of CR-22 to the intersection of SR-8 (US-80) (Site 1); on CR-57 from the junction of CR-59 to the junction of CR-54 (Site 2); and on CR-21 from the Tuskegee City Limits to the junction of SR-199 (Site 3). Length 7.662 mi.

The Bracket Estimate on this project is from \$752,905 to \$920,217.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
401A006	49,038	SQYD	Bituminous Treatment G
405A000	4,328	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A336	4,961	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A346	1,200	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,775	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 42,200.00).
701A030	11	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	8	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	6	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	25	Mile	Solid Temporary Traffic Stripe
703A004	162	SQFT	Traffic Control Markings, Class 2T, Type A
703D001	162	SQFT	Temporary Traffic Control Markings
705A032	178	Each	Pavement Markers, Class A-H, Type 1-B
705A037	692	Each	Pavement Markers, Class A-H, Type 2-D
740B000	421	SQFT	Construction Signs
740O000	1	Each	Pilot Car