

Alabama Department of Transportation
Proposal Item Summary

094. STPNU-6415(250)

WALKER COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 8.00

for constructing the Resurfacing, Guardrail Replacement, and Traffic Stripe on New Oakman Highway from the junction of Market Street in Oakman to the Right-of-Way of SR-269 in Parrish. Length 7.270 mi.

The Bracket Estimate on this project is from \$1,384,785 to \$1,692,515.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	325 LF		Removing Guardrail
206E019	48 Each		Removing Guardrail End Anchor (Type 10)
210D001	200 CUYD		Borrow Excavation (Loose Truckbed Measurement)
401B103	168,770 SQYD		Bituminous Treatment J (With Polymer Additive)
401B108	33,012 SQYD		Bituminous Treatment G (With Polymer Additive)
405A000	10,274 Gal		Tack Coat
407B000	8 Mile		Joint Sealant For Hot Mix Asphalt Pavement
408A052	3,710 SQYD		Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	8,991 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	100 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B048	200 Ton		Aggregate Surfacing (1 3/4" Down, Crusher Run)
600A000	1 LS		Mobilization
610D003	67 SQYD		Filter Blanket, Geotextile
630A001	325 LF		Steel Beam Guardrail, Class A, Type 2
630C050	48 Each		Guardrail End Anchor, Type 20 Series
652A100	1 Acre		Seeding
656A010	1 Acre		Mulching
665J002	200 LF		Silt Fence
665O001	200 LF		Silt Fence Removal
665Q002	100 LF		Wattle
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 77,600.00).
701A030	16 Mile		Solid White, Class 2T, Type A Traffic Stripe
701A034	6 Mile		Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	5 Mile		Broken Yellow, Class 2T, Type A Traffic Stripe
701B007	220 LF		Dotted Class 2T, Type A, Traffic Stripe
701C000	10 Mile		Broken Temporary Traffic Stripe
701C001	12 Mile		Solid Temporary Traffic Stripe
703A004	2,975 SQFT		Traffic Control Markings, Class 2T, Type A
703B004	23 SQFT		Traffic Control Legends, Class 2T, Type A
703D001	2,550 SQFT		Temporary Traffic Control Markings
705A032	220 Each		Pavement Markers, Class A-H, Type 1-B
705A037	400 Each		Pavement Markers, Class A-H, Type 2-D
740B000	422 SQFT		Construction Signs

Item No.	Quantity	Units	Description
740D000	50	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car