

**Alabama Department of Transportation
Proposal Item Summary**

011. ACBRZ60401-ATRP(012)

COOSA COUNTY

Contract Time: 80 Working Days

for constructing the Bridge Replacement and Approaches on CR-107 over Jack Creek northwest of Rockford. Length 0.056 mi.

The Bracket Estimate on this project is from \$326,279 to \$398,786.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|-----------------|-----------------|--------------|---|
| 201A002 | 1 | LS | Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre) |
| 206A000 | 1 | LS | Removal Of Old Bridge, Station 5+00.64 |
| 210A000 | 714 | CUYD | Unclassified Excavation |
| 214A000 | 513 | CUYD | Structure Excavation |
| 214B001 | 156 | CUYD | Foundation Backfill, Commercial |
| 231B001 | 84 | Ton | Roadbed Stabilizing Material, ALDOT #467 |
| 502A000 | 51,072 | LB | Steel Reinforcement |
| 524A010 | 192 | CUYD | Culvert Concrete |
| 600A000 | 1 | LS | Mobilization |
| 602A000 | 14 | Each | Right Of Way Markers |
| 610C001 | 325 | Ton | Loose Riprap, Class 2 |
| 610D003 | 257 | SQYD | Filter Blanket, Geotextile |
| 650A000 | 74 | CUYD | Topsoil |
| 652A100 | 1 | Acre | Seeding |
| 656A010 | 1 | Acre | Mulching |
| 665F000 | 120 | Each | Hay Bales |
| 665J002 | 600 | LF | Silt Fence |
| 665O001 | 600 | LF | Silt Fence Removal |
| 680A001 | 1 | LS | Geometric Controls |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 13,000.00) |
| 740B000 | 182 | SQFT | Construction Signs |
| 740F002 | 10 | Each | Barricades, Type III |
| 740I002 | 5 | Each | Warning Lights, Type B |