

**Alabama Department of Transportation
Proposal Item Summary**

021. NH-0006(566)

BIBB COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-6 (US-82) from the SR-5 Interchange (MP 81.517) to the Walter Owens Bridge (MP 83.236) in Centreville. Length 1.718 mi.

The Bracket Estimate on this project is from \$1,270,485 to \$1,552,815.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
305B077	212	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	12,034	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	54,277	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A054	34,328	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A360	6,475	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	1,614	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	3,026	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	577	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	7	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 72,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	136	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B207	3,560	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	19	Mile	Solid Temporary Traffic Stripe
701G142	860	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	664	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	664	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,328	LF	Solid Traffic Stripe Removed (Plastic)
701H006	860	LF	Broken Traffic Stripe Removed (Plastic)
701H011	136	LF	Dotted Traffic Stripe Removed (Plastic)
703A002	4,476	SQFT	Traffic Control Markings, Class 2, Type A
703B002	269	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,476	SQFT	Temporary Traffic Control Markings

Item No.	Quantity	Units	Description
705A030	280	Each	Pavement Markers, Class A-H, Type 2-C
705A031	240	Each	Pavement Markers, Class A-H, Type 1-A
728A000	2	Each	Truck Mounted Impact Attenuator Unit
740B000	1,770	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	5	Each	Portable Sequential Arrow And Chevron Sign Unit