

**Alabama Department of Transportation
Proposal Item Summary**

029. SRTS-SR10(918)

JEFFERSON COUNTY

Contract Time: 45 Working Days

for constructing the Sidewalks and Improvements along various routes at Leeds Middle School in Leeds. Length 0.372 mi.

The Bracket Estimate on this project is from \$169,117 to \$206,699.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206C000	40	SQYD	Removing Concrete Sidewalk
206C010	226	SQYD	Removing Concrete Driveway
206D003	60	LF	Removing Curb And Gutter
600A000	1	LS	Mobilization
618A000	847	SQYD	Concrete Sidewalk, 4" Thick
618B003	308	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
623C003	20	LF	Combination Curb & Gutter, Type C (Modified)
654A000	668	SQYD	Solid Sodding
665J002	1,600	LF	Silt Fence
665O001	1,600	LF	Silt Fence Removal
665P005	3	Each	Inlet Protection, Stage 3 Or 4
665Q002	30	LF	Wattle
674A000	150	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
703A002	1,117	SQFT	Traffic Control Markings, Class 2, Type A
703C000	364	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
711A000	1	LS	Roadway Sign Relocation
740B000	198	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone