

**Alabama Department of Transportation  
Proposal Item Summary**

**031. STPAA-0028(510)**

**MARENGO COUNTY**

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-28 from the junction of Lawrence Street in Linden to west of the junction of Airport Road (MP 48.000). Length 4.601 mi.

The Bracket Estimate on this project is from \$986,253 to \$1,205,420.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
401B100	69,129	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	2,000	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	87,675	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	7,869	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	415	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	10	Mile	Scoring Bituminous Pavement Surface
430B043	500	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	600	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	46	Acre	Mowing
656A010	3	Acre	Mulching
665J002	850	LF	Silt Fence
665O001	850	LF	Silt Fence Removal
665Q002	350	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 53,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C002	14	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	51	Mile	Solid Temporary Traffic Stripe (Paint)
701G146	738	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	369	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	738	LF	Solid Traffic Stripe Removed (Plastic)
701H006	369	LF	Broken Traffic Stripe Removed (Plastic)
703A002	360	SQFT	Traffic Control Markings, Class 2, Type A
705A032	150	Each	Pavement Markers, Class A-H, Type 1-B
705A037	400	Each	Pavement Markers, Class A-H, Type 2-D
740B000	432	SQFT	Construction Signs

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car