

**Alabama Department of Transportation  
Proposal Item Summary**

---

**034. STPAA-0036(508)**

**LAWRENCE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 9.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-36 from the intersection of SR-157 south of Oakville to the Morgan County Line. Length 3.002 mi.

The Bracket Estimate on this project is from \$717,197 to \$876,574.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
209A000	3	Each	Mailbox Reset, Single
305B077	956	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	5,146	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	52,648	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A360	4,080	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	600	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	2,069	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 40,200.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	21	Mile	Solid Temporary Traffic Stripe
701G251	300	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	1,176	SQFT	Traffic Control Markings, Class 2, Type A
703D001	260	SQFT	Temporary Traffic Control Markings
705A030	23	Each	Pavement Markers, Class A-H, Type 2-C
705A032	12	Each	Pavement Markers, Class A-H, Type 1-B
705A037	206	Each	Pavement Markers, Class A-H, Type 2-D
740B000	840	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car