

**Alabama Department of Transportation  
Proposal Item Summary**

**035. STPAA-0104(510)**

**BALDWIN COUNTY**

Contract Time: 75 Working Days

DBE Goal Percent: 6.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-104 from the junction of SR-42 (US-98) in Fairhope to the junction of SR-59 in Robertsdale. Length 10.490 mi.

The Bracket Estimate on this project is from \$1,523,790 to \$1,862,410.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	19,354	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	193,533	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	13,908	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,092	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
650A000	750	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	162	Acre	Mowing
656A010	5	Acre	Mulching
665G000	250	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 40,000.00)
701A227	24	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	17	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,786	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	40	Mile	Solid Temporary Traffic Stripe
701G146	574	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	287	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	574	LF	Solid Traffic Stripe Removed (Plastic)
701H006	287	LF	Broken Traffic Stripe Removed (Plastic)
703A002	8,639	SQFT	Traffic Control Markings, Class 2, Type A
703B002	767	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,839	SQFT	Temporary Traffic Control Markings
703E001	431	SQFT	Temporary Traffic Control Legends
705A030	114	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,307	Each	Pavement Markers, Class A-H, Type 1-B

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A037	884	Each	Pavement Markers, Class A-H, Type 2-D
705A038	780	Each	Pavement Markers, Class A-H, Type 2-E
730H001	8,050	LF	Loop Wire
730L005	200	LF	2", Non-Metallic, Conduit
740B000	723	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
745A000	400	HOUR	Uniformed Police Officer