

**Alabama Department of Transportation  
Proposal Item Summary**

**042. STPAA-HSIP-0014(537)**

**AUTAUGA COUNTY**

Contract Time: 80 Working Days

DBE Goal Percent: 5.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-14 from the junction of CR-21 in Autaugaville to the junction of SR-6 (US-82) in Prattville. Length 9.495 mi.

The Bracket Estimate on this project is from \$3,716,698 to \$4,524,631.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	224	LF	Removing Guardrail
206E008	24	Each	Removing Guardrail End Anchor (All Type)
210A000	350	CUYD	Unclassified Excavation
210D021	2,000	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	850	STA	Machine Grading Shoulders
305B077	500	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A004	165,000	SQYD	Bituminous Treatment E
405A000	13,500	Gal	Tack Coat
407B000	19	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	47,000	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A053	130,000	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	12,050	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	2,200	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	17,250	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B693	3,600	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	19	Mile	Scoring Bituminous Pavement Surface
502A000	870	LB	Steel Reinforcement
600A000	1	LS	Mobilization
610D003	335	SQYD	Filter Blanket, Geotextile
620A000	7	CUYD	Minor Structure Concrete
630A001	225	LF	Steel Beam Guardrail, Class A, Type 2
630C003	12	Each	Guardrail End Anchor, Type 13
630C050	11	Each	Guardrail End Anchor, Type 20 Series
630C070	1	Each	Guardrail End Anchor, Type 10 Series
650A000	3,000	CUYD	Topsoil
652A100	16	Acre	Seeding
652C000	16	Acre	Mowing
654A000	250	SQYD	Solid Sodding
656A010	16	Acre	Mulching

Item No.	Quantity	Units	Description
659C002	500	SQYD	Erosion Control Product, Type S2
665A000	16	Acre	Temporary Seeding
665B001	48	Ton	Temporary Mulching
665F000	100	Each	Hay Bales
665G000	100	Each	Sand Bags
665J002	2,400	LF	Silt Fence
665O001	2,400	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	16	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 208,000.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,475	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	68	Mile	Solid Temporary Traffic Stripe
701G146	412	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	206	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	206	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	618	LF	Solid Traffic Stripe Removed (Plastic)
701H006	206	LF	Broken Traffic Stripe Removed (Plastic)
703A002	10,500	SQFT	Traffic Control Markings, Class 2, Type A
703B002	292	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,500	SQFT	Temporary Traffic Control Markings
705A030	140	Each	Pavement Markers, Class A-H, Type 2-C
705A031	150	Each	Pavement Markers, Class A-H, Type 1-A
705A032	150	Each	Pavement Markers, Class A-H, Type 1-B
705A037	530	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,504	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit