

**Alabama Department of Transportation
Proposal Item Summary**

043. STPAA-HSIP-0169(502)

RUSSELL COUNTY

Contract Time: 50 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-169 from the junction of SR-1 (US-431) north of Seale to the junction of SR-8 (US-80) in Crawford. Length 9.704 mi.

The Bracket Estimate on this project is from \$1,761,920 to \$2,153,458.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	1,012	STA	Machine Grading Shoulders
401B108	157,500	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	1,600	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A054	1,700	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
410H000	1	Each	Material Remixing Device
424A356	9,100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	1,300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	2,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	2,100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	20	Mile	Scoring Bituminous Pavement Surface
430B043	5,000	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	335	SQYD	Filter Blanket, Geotextile
650A000	500	CUYD	Topsoil
652A100	19	Acre	Seeding
652C000	19	Acre	Mowing
654A000	250	SQYD	Solid Sodding
656A010	19	Acre	Mulching
659C002	500	SQYD	Erosion Control Product, Type S2
665A000	19	Acre	Temporary Seeding
665B001	57	Ton	Temporary Mulching
665F000	100	Each	Hay Bales
665G000	100	Each	Sand Bags
665J002	2,875	LF	Silt Fence
665O001	2,875	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	19	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 94,500.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	115	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	73	Mile	Solid Temporary Traffic Stripe
701G146	1,286	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	643	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
701H001	1,286	LF	Solid Traffic Stripe Removed (Plastic)
701H006	643	LF	Broken Traffic Stripe Removed (Plastic)
703A002	1,560	SQFT	Traffic Control Markings, Class 2, Type A
703B002	80	SQFT	Traffic Control Legends, Class 2, Type A
703D001	340	SQFT	Temporary Traffic Control Markings
705A032	210	Each	Pavement Markers, Class A-H, Type 1-B
705A037	920	Each	Pavement Markers, Class A-H, Type 2-D
705A038	326	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,706	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car