

**Alabama Department of Transportation
Proposal Item Summary**

048. STPBH-0003(593)

JEFFERSON COUNTY

Contract Time: 170 Working Days

DBE Goal Percent: 2.00

for constructing the Roadway Lighting Improvements on SR-3 (US-31) from the Cahaba River to the junction of Patton Chapel Road in Hoover. Length 1.490 mi.

The Bracket Estimate on this project is from \$1,067,396 to \$1,304,595.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$21.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
600A000	1	LS	Mobilization
610D003	1,000	SQYD	Filter Blanket, Geotextile
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665G000	330	Each	Sand Bags
665J002	3,420	LF	Silt Fence
665O001	3,420	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 34,000.00)
740B000	621	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750B602	66	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750B607	8	Each	Roadway Luminaire Assembly with Two, LED, 400 Watt Equivalent Luminaire
750B612	2	Each	Roadway Luminaire Assembly with Three, LED, 400 Watt Equivalent Luminaire
750C010	76	Each	Pole Foundation,Roadway
750E113	130	LF	Conduit, 1 1/4 Inch, Rigid Nonmetallic
750F026	390	LF	Conductor, #2 AWG
750G012	3,650	LF	Combined Duct And Cable, 4 #6 AWG/ 1 #6 AWG GND
750G022	3,485	LF	Combined Duct And Cable, 4 #4 AWG/ 1 #6 AWG GND
750G024	965	LF	Combined Duct And Cable, 6 #4 AWG/ 1 #6 AWG GND
750G032	3,590	LF	Combined Duct and Cable, 4 #2 AWG/ 1 #6 AWG GND
750G034	4,455	LF	Combined Duct and Cable, 6 #2 AWG/ 1 #6 AWG GND
750H005	7	Each	Service Pole
750I015	7	Each	Lighting Control Center
751J006	52	Each	Remove Luminaire Pole Foundation, Concrete
751L002	5	Each	Remove Lighting Control Center, 6 Circuit
751L025	52	Each	Remove Roadway Luminaire Assembly
751M000	1	LS	Remove Conductors
756A022	2,570	LF	4" Electrical Conduit, 1 Line, Type 5 Installation