

**Alabama Department of Transportation
Proposal Item Summary**

055. STPNU-0415(256)

BIBB COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-36 from the intersection of SR-139 to the Chilton County Line east of Randolph. Length 2.195 mi.

The Bracket Estimate on this project is from \$594,535 to \$726,654.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B108	29,000	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	2,825	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	3,050	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	2,350	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	450	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B672	610	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B678	380	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	950	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 31,000.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	9	Mile	Solid Temporary Traffic Stripe
703A002	264	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
705A032	25	Each	Pavement Markers, Class A-H, Type 1-B
705A037	285	Each	Pavement Markers, Class A-H, Type 2-D
740B000	375	SQFT	Construction Signs
740O000	1	Each	Pilot Car