

Alabama Department of Transportation
Proposal Item Summary

056. STPOA-3016(251) & STPNU-3016(250)

FRANKLIN COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 7.00

for constructing the Resurfacing and Traffic Stripe on CR-624 from the junction of SR-24 to the junction of West Lawrence Street in Russellville (Site 1) and on CR-44 from the junction of CR-244 to the junction of SR-24 in Russellville (Site 2). Length 4.079 mi.

The Bracket Estimate on this project is from \$504,736 to \$616,899.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	228	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
401A008	35,873	SQYD	Bituminous Treatment J
405A000	1,450	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	10,874	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	3,691	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	1,089	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B014	1,068	Ton	Aggregate Surfacing (ALDOT #410 Modified)
600A000	1	LS	Mobilization
630A004	228	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C050	4	Each	Guardrail End Anchor, Type 20 Series
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 30,100.00)
701A030	8	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	8	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701C001	10	Mile	Solid Temporary Traffic Stripe
705A037	539	Each	Pavement Markers, Class A-H, Type 2-D
740B000	500	SQFT	Construction Signs
740E000	20	Each	Cones (36 Inches High)
740M001	20	Each	Ballast For Cone
740O000	1	Each	Pilot Car