

**Alabama Department of Transportation
Proposal Item Summary**

059. STPOA-9059(601)

LEE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 8.00

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-82 (Donahue Drive) from the junction of Cary Drive to the intersection of SR-147 (Shug Jordan Parkway) in Auburn. Length 1.050 mi.

The Bracket Estimate on this project is from \$563,641 to \$688,894.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206C000	100	SQYD	Removing Concrete Sidewalk
206D003	300	LF	Removing Curb And Gutter
405A000	3,087	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A051	4,641	SQYD	Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
408A052	19,191	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A360	1,812	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	695	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618A000	860	SQYD	Concrete Sidewalk, 4" Thick
618A001	125	SQYD	Concrete Sidewalk, 6" Thick
620A000	5	CUYD	Minor Structure Concrete
623C003	300	LF	Combination Curb & Gutter, Type C (Modified)
641S500	17	Each	Valve Box Reset
645K500	7	Each	Manhole Frame And Cover Reset
654A000	688	SQYD	Solid Sodding
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665P005	4	Each	Inlet Protection, Stage 3 Or 4
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 30,500.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	810	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	6	Mile	Solid Temporary Traffic Stripe
701G253	621	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
703A002	1,820	SQFT	Traffic Control Markings, Class 2, Type A
703B002	160	SQFT	Traffic Control Legends, Class 2, Type A
703D001	650	SQFT	Temporary Traffic Control Markings
705A030	50	Each	Pavement Markers, Class A-H, Type 2-C
705A032	73	Each	Pavement Markers, Class A-H, Type 1-B
705A037	175	Each	Pavement Markers, Class A-H, Type 2-D
705A038	38	Each	Pavement Markers, Class A-H, Type 2-E
710A099	77	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Background)
710B001	360	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
740B000	335	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone