

**Alabama Department of Transportation  
Proposal Item Summary**

**008. ACBRZ59414-ATRP(010)**

**CALHOUN COUNTY**

Contract Time: 130 Working Days

DBE Goal Percent: 6.00

for constructing the Bridge Replacement (Grade, Drain, Base, and Pave) on CR-567 (Verbon George Road) over Ohatchee Creek southeast of Glencoe. Length 0.212 mi.

The Bracket Estimate on this project is from \$1,129,467 to \$1,380,459.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$16.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 6+11.46
206D000	121	LF	Removing Pipe
206D011	1,011	LF	Removing Fence
206E000	2	Each	Removing Headwalls
210A000	7,404	CUYD	Unclassified Excavation
210D001	4,456	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	70	CUYD	Structure Excavation
214B001	65	CUYD	Foundation Backfill, Commercial
230A000	10	RBST	Roadbed Processing
301A012	2,732	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,732	SQYD	Bituminous Treatment A
405A000	330	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	184	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	316	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
430B000	55	Ton	Aggregate Surfacing (ALDOT #467 Or #57)
430B043	75	Ton	Aggregate Surfacing (1" Down, Crusher Run)
450B000	125	SQYD	Reinforced Cement Concrete Bridge End Slab
502A000	22,600	LB	Steel Reinforcement
502B000	1	LS	Steel Reinforcement For Bridge Superstructure, Station 5+95.00, Approximately 35,200 lbs
506A005	52	LF	Drilled Shaft Excavation, 3'-6" Diameter
506A008	10	LF	Drilled Shaft Excavation, 4'-0" Diameter
506B002	14	LF	Special Drilled Shaft Excavation, 3'-6" Diameter
506B003	8	LF	Special Drilled Shaft Excavation, 4'-0" Diameter
506C041	66	LF	Drilled Shaft Construction, 3'-6" Diameter, Class DS1 Concrete
506C042	35	LF	Drilled Shaft Construction, 4'-0" Diameter, Class DS1 Concrete
506D000	14	LF	Exploration Below Drilled Shaft
506F008	27	LF	Permanent Drilled Shaft Casing, 4'-0" Diameter
506G001	1	Each	Crosshole Sonic Logging, 3'-6" Diameter
506G002	1	Each	Crosshole Sonic Logging, 4'-0" Diameter
508A000	4,480	LB	Structural Steel
510A007	72	CUYD	Bridge Substructure Concrete
510C051	1	LS	Bridge Concrete Superstructure, Station 5+95.00, Approximately 139 Cubic Yards
510E000	429	SQYD	Grooving Concrete Bridge Decks

Item No.	Quantity	Units	Description
511A072	16	Each	Elastomeric Bearing Type 4 (Mark VB3)
513B005	588	LF	Pretensioned-Prestressed Concrete Girders, Type III (Specialty Item)
530A004	115	LF	36" Roadway Pipe (Class 3 R.C.)
535B009	64	LF	18" Span, 11" Rise Side Drain Pipe
600A000	1	LS	Mobilization
602A000	17	Each	Right Of Way Markers
610C001	1,567	Ton	Loose Riprap, Class 2
610D003	1,974	SQYD	Filter Blanket, Geotextile
619A005	2	Each	36" Roadway Pipe End Treatment, Class 1
619B115	4	Each	18" Span, 11" Rise Side Drain Pipe End Treatment, Class 1
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630C003	4	Each	Guardrail End Anchor, Type 13
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	876	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
659C002	669	SQYD	Erosion Control Product, Type S2
659C004	407	SQYD	Erosion Control Product, Type C2
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665I000	220	Ton	Temporary Riprap, Class 2
665J002	2,404	LF	Silt Fence
665N000	45	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	2,404	LF	Silt Fence Removal
665Q002	200	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 58,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701G146	300	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	300	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
705A037	27	Each	Pavement Markers, Class A-H, Type 2-D
740B000	179	SQFT	Construction Signs
740C000	68	SQFT	Special Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B