

**Alabama Department of Transportation
Proposal Item Summary**

010. ACBRZ60915-ATRP(007)

LAMAR COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 5.00

for constructing the Bridge Replacement and Approaches on CR-412 (Sunset Road) over Little Hell's Creek. Length 0.105 mi.

The Bracket Estimate on this project is from \$288,961 to \$353,174.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 14+78.06
210A000	36	CUYD	Unclassified Excavation
210D021	618	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
230A000	6	RBST	Roadbed Processing
301A090	230	SQYD	Soil Aggregate Base Course, Type A, Road Mixed, 3" Compacted Thickness
301A098	2,130	SQYD	Soil Aggregate Base Course, Type A, Road Mixed, 5" Compacted Thickness
505A002	1	Each	Steel Test Piles (HP 12x53)
505B057	1	Each	Static Loading Tests (HP 12x53)
505M002	812	LF	Steel Piling Furnished And Driven (HP 12x53)
507A000	2	Each	Wire Rope Abutment Anchor Assembly
511A000	20	Each	Elastomeric Bearing Type 1
512A008	2	Each	Precast Concrete Abutment Caps, 2'-0" Wide By 1'-7" Deep By 28'-0" Long
512C017	5	Each	Precast Concrete Type 1 Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512C025	2	Each	Precast Concrete Type 2C Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512D031	2	Each	Precast Concrete Barrier Rail End Section, 39'-11 3/8" Long (Modified)
512E013	16	Each	Precast Concrete Abutment Panels, Type A3, 6'-1" Long
512F002	8	Each	Precast Concrete Wing Panels, Type W3
512G000	4	Each	Precast Concrete Abutment Wing Cap Panels
600A000	1	LS	Mobilization
610C001	160	Ton	Loose Riprap, Class 2
610D003	160	SQYD	Filter Blanket, Geotextile
630C003	4	Each	Guardrail End Anchor, Type 13
630C070	4	Each	Guardrail End Anchor, Type 10 Series
650A000	125	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665I000	40	Ton	Temporary Riprap, Class 2
665J002	1,100	LF	Silt Fence
665O001	1,100	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 12,000.00)
740B000	141	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III

Item No.	Quantity	Units	Description
740I002	4 Each		Warning Lights, Type B