

**Alabama Department of Transportation  
Proposal Item Summary**

---

**024. ERPR-9010(138)**

**CONECUH COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 10.00

for constructing the Slope Repair (Front Slope Failure) on I-65 at MP 77.600 (Northbound Lane) southeast of Range. Length 0.189 mi.

The Bracket Estimate on this project is from \$106,473 to \$130,134.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206D001	1,013	LF	Removing Guardrail
206E008	2	Each	Removing Guardrail End Anchor (All Type)
210A000	100	CUYD	Unclassified Excavation
600A000	1	LS	Mobilization
610C001	516	Ton	Loose Riprap, Class 2
610D003	399	SQYD	Filter Blanket, Geotextile
630A001	1,013	LF	Steel Beam Guardrail, Class A, Type 2
630C001	1	Each	Guardrail End Anchor, Type 8
630C050	1	Each	Guardrail End Anchor, Type 20 Series
635A000	150	LF	Woven Wire Fence
650A000	49	CUYD	Topsoil
654A001	394	SQYD	Solid Sodding (Bermuda)
665B001	1	Ton	Temporary Mulching
665E000	272	SQYD	Polyethylene
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	80	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 8,000.00)
740B000	795	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
741C001	1	Each	Portable Sequential Arrow And Chevron Sign Unit (Truck Mounted)