

**Alabama Department of Transportation
Proposal Item Summary**

027. IM-I020(352)

TALLADEGA COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-20 from east of the CR-97 Overpass (Airport Road) at MP 173.218 in Lincoln to west of the H. J. Bentley Jr. Parkway Overpass at MP 181.747 near Oxford. Length 8.529 mi.

The Bracket Estimate on this project is from \$4,172,999 to \$5,100,332.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	765	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	407,000	SQYD	Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
420A015	17,700	Ton	Polymer Modified Open Graded Friction Course
420B000	70,700	Gal	Open Graded Friction Course Tack Coat
424A356	850	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
432A000	228,000	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 223,000.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	35	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	7,500	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	35	Mile	Broken Temporary Traffic Stripe
701C001	36	Mile	Solid Temporary Traffic Stripe
701G142	1,845	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	925	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	925	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,845	LF	Solid Traffic Stripe Removed (Tape)
701H007	1,845	LF	Broken Traffic Stripe Removed (Tape)
703A002	7,850	SQFT	Traffic Control Markings, Class 2, Type A
703B002	200	SQFT	Traffic Control Legends, Class 2, Type A
705A030	2,350	Each	Pavement Markers, Class A-H, Type 2-C
705A031	1,200	Each	Pavement Markers, Class A-H, Type 1-A
705A032	750	Each	Pavement Markers, Class A-H, Type 1-B
740B000	3,281	SQFT	Construction Signs
740C000	24	SQFT	Special Construction Signs
740D000	650	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2