

**Alabama Department of Transportation
Proposal Item Summary**

037. NH-0021(558)

CALHOUN COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-21 from 0.100 mile north of the intersection of George Douthit Drive Southwest to 0.250 mile north of the junction of Pine Island Road in Jacksonville. Length 4.477 mi.

The Bracket Estimate on this project is from \$1,481,690 to \$1,810,954.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
206D001	100 LF	Removing Guardrail
206E008	1 Each	Removing Guardrail End Anchor (All Type)
401B100	148,000 SQYD	Bituminous Treatment E (With Polymer Additive)
401B108	24,500 SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	7,500 Gal	Tack Coat
407B000	16 Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	155,500 SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1 Each	Material Remixing Device
410J000	1 Each	Smoothness Data Collection, Certified Inertial Profiler
424A360	11,500 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	930 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	500 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500 Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1 LS	Mobilization
630A001	100 LF	Steel Beam Guardrail, Class A, Type 2
630C001	1 Each	Guardrail End Anchor, Type 8
630C050	1 Each	Guardrail End Anchor, Type 20 Series
665G000	50 Each	Sand Bags
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 98,000.00)
701A227	9 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2 Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	6,000 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	21 Mile	Broken Temporary Traffic Stripe
701C001	39 Mile	Solid Temporary Traffic Stripe
703A002	9,800 SQFT	Traffic Control Markings, Class 2, Type A
703B002	575 SQFT	Traffic Control Legends, Class 2, Type A
703D001	7,400 SQFT	Temporary Traffic Control Markings
705A030	750 Each	Pavement Markers, Class A-H, Type 2-C
705A032	525 Each	Pavement Markers, Class A-H, Type 1-B
705A037	625 Each	Pavement Markers, Class A-H, Type 2-D
705A038	175 Each	Pavement Markers, Class A-H, Type 2-E

Item No.	Quantity	Units	Description
740B000	2,617	SQFT	Construction Signs
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit