

**Alabama Department of Transportation
Proposal Item Summary**

046. STPAA-0027(513)

GENEVA COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 6.00

for constructing the Resurfacing and Traffic Stripe on SR-27 from the junction of CR-8 (Goose Hollow Road) to the Coffee County Line. Length 9.331 mi.

The Bracket Estimate on this project is from \$2,870,596 to \$3,508,506.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	837	SQYD	Removing Concrete Driveway
209A000	12	Each	Mailbox Reset, Single
210D021	1,824	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	978	STA	Machine Grading Shoulders
405A000	24,345	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	162,862	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A361	13,411	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	55	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	16,139	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	400	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" MAXimum Aggregate Size mix, ESAL Range C/D
428A001	17	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	5,429	CUYD	Topsoil
652A100	28	Acre	Seeding
652C000	80	Acre	Mowing
656A010	28	Acre	Mulching
665A000	28	Acre	Temporary Seeding
665B001	28	Ton	Temporary Mulching
665J002	1,200	LF	Silt Fence
665O001	1,200	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
666A001	28	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 150,330.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	351	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701C000	23	Mile	Broken Temporary Traffic Stripe
701C001	65	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	1,934	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,262	SQFT	Temporary Traffic Control Markings
705A030	255	Each	Pavement Markers, Class A-H, Type 2-C
705A032	585	Each	Pavement Markers, Class A-H, Type 1-B
705A037	983	Each	Pavement Markers, Class A-H, Type 2-D
705A038	130	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,454	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car