

**Alabama Department of Transportation  
Proposal Item Summary**

**047. STPAA-0092(501)**

**DALE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on SR-85/SR-92 from the east end of the bridge over Claybank Creek to the west end of the bridge over Choctawhatchee Creek in Clayhatchee. Length 2.885 mi.

The Bracket Estimate on this project is from \$660,328 to \$807,067.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	6,260	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	83,454	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A360	5,634	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	1	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 34,435.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,820	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	2,314	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	1,157	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	2,710	SQFT	Traffic Control Markings, Class 2, Type A
703B002	157	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,622	SQFT	Temporary Traffic Control Markings
705A030	80	Each	Pavement Markers, Class A-H, Type 2-C
705A032	370	Each	Pavement Markers, Class A-H, Type 1-B
705A037	610	Each	Pavement Markers, Class A-H, Type 2-D
705A038	300	Each	Pavement Markers, Class A-H, Type 2-E
740B000	493	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone

Item No.	Quantity	Units	Description
740000	1 Each	Pilot Car	