

**Alabama Department of Transportation
Proposal Item Summary**

054. STPAA-HSIP-0015(529)

CHAMBERS COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-15 (US-29) from the Lee County Line to just south of the junction of Judge Brown Road (MP 204.558). Length 3.312 mi.

The Bracket Estimate on this project is from \$728,081 to \$889,877.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	4	Each	Mailbox Reset, Single
401B100	51,000	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	2,600	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	51,300	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A340	4,500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A349	50	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	1,360	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	7	Mile	Scoring Bituminous Pavement Surface
430B043	450	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	150	SQYD	Filter Blanket, Geotextile
665A000	4	Acre	Temporary Seeding
665B001	12	Ton	Temporary Mulching
665G000	100	Each	Sand Bags
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	210	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 46,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	36	Mile	Solid Temporary Traffic Stripe
703A002	250	SQFT	Traffic Control Markings, Class 2, Type A
703D001	750	SQFT	Temporary Traffic Control Markings
705A032	75	Each	Pavement Markers, Class A-H, Type 1-B
705A037	350	Each	Pavement Markers, Class A-H, Type 2-D

Item No.	Quantity	Units	Description
740B000	916	SQFT	Construction Signs
740O000	1	Each	Pilot Car