

**Alabama Department of Transportation
Proposal Item Summary**

063. STPNU-2417(250)

DALLAS COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-43 from 0.400 mile south of the junction of CR-420 to the junction of SR-8 (US-80). Length 1.862 mi.

The Bracket Estimate on this project is from \$347,297 to \$424,474.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	2,186	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	1,699	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	1,893	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	275	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	729	CUYD	Topsoil
652A100	3	Acre	Seeding
656A010	3	Acre	Mulching
665F000	180	Each	Hay Bales
665J002	900	LF	Silt Fence
665O001	900	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 19,500.00)
701A231	4	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C002	1	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	7	Mile	Solid Temporary Traffic Stripe (Paint)
701G251	250	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	108	SQFT	Traffic Control Markings, Class 2, Type A
703D002	216	SQFT	Temporary Traffic Control Markings (Paint)
705A032	43	Each	Pavement Markers, Class A-H, Type 1-B
705A037	204	Each	Pavement Markers, Class A-H, Type 2-D
740B000	290	SQFT	Construction Signs
740O000	1	Each	Pilot Car