

**Alabama Department of Transportation
Proposal Item Summary**

064. STPNU-2916(251)

FAYETTE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 10.00

for constructing the Resurfacing, Guardrail, and Traffic Stripe on CR-35 from the junction of Oak Grove Road to the South City Limits of Fayette. Length 3.257 mi.

The Bracket Estimate on this project is from \$674,057 to \$823,847.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
206D001	1,820 LF	Removing Guardrail
206E008	20 Each	Removing Guardrail End Anchor (All Type)
210D015	1,500 CU YD	Borrow Excavation (A-4) (Loose Truckbed Measurement)
404G001	36,202 SQ YD	Pavement Surfacing (Scrub Seal)
405A000	400 Gal	Tack Coat
409A001	36,202 SQ YD	Triple Layer Bituminous Treatment
424B640	200 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300 Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	700 Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS	Mobilization
610C001	3,336 Ton	Loose Riprap, Class 2
610D003	2,571 SQ YD	Filter Blanket, Geotextile
630A001	50 LF	Steel Beam Guardrail, Class A, Type 2
630A004	1,820 LF	Steel Beam Guardrail, Class B, Type 2
630C001	2 Each	Guardrail End Anchor, Type 8
630C022	20 Each	Guardrail End Anchor, Type Special
630C050	16 Each	Guardrail End Anchor, Type 20 Series
630C070	2 Each	Guardrail End Anchor, Type 10 Series
665J002	1,600 LF	Silt Fence
665O001	1,600 LF	Silt Fence Removal
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 37,800.00)
701A030	7 Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	5 Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	2 Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	2 Mile	Broken Temporary Traffic Stripe
701C001	5 Mile	Solid Temporary Traffic Stripe
705A032	60 Each	Pavement Markers, Class A-H, Type 1-B
705A037	390 Each	Pavement Markers, Class A-H, Type 2-D
740B000	375 SQ FT	Construction Signs
740E000	50 Each	Cones (36 Inches High)
740M001	50 Each	Ballast For Cone
740O000	1 Each	Pilot Car