

**Alabama Department of Transportation
Proposal Item Summary**

065. STPNU-4014(252) & STPNU-4014(251)

LAWRENCE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 10.00

for constructing the Resurfacing and Traffic Stripe on CR-21, CR-20, CR-17, and CR-28 from the junction of CR-23 to the junction of CR-460 and on CR-214 from the junction of SR-33 to the junction of CR-217 east of Langtown. Length 9.518 mi.

The Bracket Estimate on this project is from \$690,404 to \$843,827.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	120	LF	Removing Guardrail
206E019	4	Each	Removing Guardrail End Anchor (Type 10)
401B106	63,985	SQYD	Bituminous Treatment JG (With Polymer Additive)
405A000	3,432	Gal	Tack Coat
409A001	47,286	SQYD	Triple Layer Bituminous Treatment
424B642	1,706	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,651	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A001	243	LB	Steel Reinforcement (Grade 60)
524B010	6	CUYD	Culvert Concrete Extension
600A000	1	LS	Mobilization
630A001	120	LF	Steel Beam Guardrail, Class A, Type 2
630C070	4	Each	Guardrail End Anchor, Type 10 Series
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,700.00)
701A231	20	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	29	Mile	Solid Temporary Traffic Stripe
703A002	422	SQFT	Traffic Control Markings, Class 2, Type A
705A032	233	Each	Pavement Markers, Class A-H, Type 1-B
705A037	815	Each	Pavement Markers, Class A-H, Type 2-D
740B000	568	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	2	Each	Pilot Car