

**Alabama Department of Transportation
Proposal Item Summary**

066. STPNU-4216(251)

LIMESTONE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 6.00

for constructing the Resurfacing (Triple Layer Bituminous Surface Treatment) and Traffic Stripe on Parker Road from the junction of SR-2 (US-72) to the junction of New Cut Road (Site 1); on Baker Hill Road from the junction of New Cut Road to the junction of Elk River Mills Road (Site 2); and on Elk River Mills Road from the junction of Baker Hill Road to the Elk River Bridge (Site 3) west of Athens. Length 4.301 mi.

The Bracket Estimate on this project is from \$484,006 to \$591,563.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B100	32,625	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	1,910	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
409A001	20,812	SQYD	Triple Layer Bituminous Treatment
424A340	2,900	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B647	360	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,652	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 27,100.00)
701A030	9	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	8	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	1	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
703A004	88	SQFT	Traffic Control Markings, Class 2T, Type A
703D001	88	SQFT	Temporary Traffic Control Markings
705A032	75	Each	Pavement Markers, Class A-H, Type 1-B
705A037	500	Each	Pavement Markers, Class A-H, Type 2-D
740B000	314	SQFT	Construction Signs
740O000	1	Each	Pilot Car