

**Alabama Department of Transportation
Proposal Item Summary**

069. STPOA-2314(250)

DALE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 8.00

for constructing the Resurfacing and Traffic Stripe on CR-10 from the intersection of SR-53 (US-231) in Grimes to the Houston County Line. Length 3.493 mi.

The Bracket Estimate on this project is from \$546,517 to \$667,965.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	341	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	369	STA	Machine Grading Shoulders
401A006	49,196	SQYD	Bituminous Treatment G
405A000	350	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A341	4,140	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	381	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
652A100	6	Acre	Seeding
652C000	6	Acre	Mowing
656A010	6	Acre	Mulching
665F000	25	Each	Hay Bales
665J002	600	LF	Silt Fence
665O001	600	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 30,300.00)
701A231	7	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	14	Mile	Solid Temporary Traffic Stripe
701G252	1,200	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	144	SQFT	Traffic Control Markings, Class 2, Type A
703B002	69	SQFT	Traffic Control Legends, Class 2, Type A
703D001	144	SQFT	Temporary Traffic Control Markings
703E001	69	SQFT	Temporary Traffic Control Legends
705A037	451	Each	Pavement Markers, Class A-H, Type 2-D
740B000	246	SQFT	Construction Signs
740O000	1	Each	Pilot Car