

**Alabama Department of Transportation  
Proposal Item Summary**

**072. STPPC-4116(251)**

**LEE COUNTY**

Contract Time: 30 Working Days

for constructing the Full Depth Reclamation, Resurfacing, and Traffic Stripe on CR-248 from the intersection of CR-243 in Smiths Station to the junction of SR-38 (US-280). Length 0.634 mi.

The Bracket Estimate on this project is from \$247,264 to \$302,212.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	72	SQYD	Removing Concrete Driveway
210D021	375	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
302A000	8,959	SQYD	Full Depth Reclamation,
302B000	135	Ton	Portland Cement For Full Depth Reclamation
401A000	8,959	SQYD	Bituminous Treatment A
401B108	8,587	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	540	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A356	450	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	716	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	23	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" MAXimum Aggregate Size mix, ESAL Range C/D
430B043	376	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665F000	50	Each	Hay Bales
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 13,900.00)
701A231	2	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	4	Mile	Solid Temporary Traffic Stripe
703A002	156	SQFT	Traffic Control Markings, Class 2, Type A
703D001	312	SQFT	Temporary Traffic Control Markings
705A037	85	Each	Pavement Markers, Class A-H, Type 2-D
740B000	453	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740F002	14	Each	Barricades, Type III
740I002	7	Each	Warning Lights, Type B
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car

