

**Alabama Department of Transportation  
Proposal Item Summary**

**031. NH-0035(530)**

**DEKALB COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 9.00

for constructing the Planing, Resurfacing, Safety Improvements, and Traffic Stripe on SR-35 from south of the junction of Deerman Avenue to south of the Northern City Limits of Rainsville (Site 1) and on SR-75 from MP 84.820 to MP 85.040 (Site 2). Length 1.920 mi.

The Bracket Estimate on this project is from \$840,910 to \$1,027,779.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	210	SQYD	Removing Concrete Sidewalk
206C010	25	SQYD	Removing Concrete Driveway
206D003	80	LF	Removing Curb And Gutter
405A000	5,849	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	73,084	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424C284	1,000	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
600A000	1	LS	Mobilization
610D003	100	SQYD	Filter Blanket, Geotextile
614A000	84	CUYD	Slope Paving
618A000	262	SQYD	Concrete Sidewalk, 4" Thick
623C000	80	LF	Combination Curb & Gutter, Type C
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 44,350.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	305	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
701G154	800	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	10,661	SQFT	Traffic Control Markings, Class 2, Type A
703B002	113	SQFT	Traffic Control Legends, Class 2, Type A
703D001	552	SQFT	Temporary Traffic Control Markings
705A030	596	Each	Pavement Markers, Class A-H, Type 2-C
705A032	263	Each	Pavement Markers, Class A-H, Type 1-B
705A037	503	Each	Pavement Markers, Class A-H, Type 2-D
705A038	132	Each	Pavement Markers, Class A-H, Type 2-E
740B000	572	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740N000	40	Each	Tubular Marker

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
741C010		2 Each	Portable Sequential Arrow And Chevron Sign Unit
423A003	AA1	1,830 Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
424A280	AA1	3,105 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
423A003	AA2	4,935 Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size