

**Alabama Department of Transportation
Proposal Item Summary**

041. STPAA-0017(572)

CHOCTAW COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-17 from the Washington County Line to the Souwilpa Creek Bridge (MP 83.998) in Silas. Length 6.039 mi.

The Bracket Estimate on this project is from \$1,359,640 to \$1,661,782.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	9	Each	Mailbox Reset, Single
401B100	91,261	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	4,619	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	119,267	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A361	9,829	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	770	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	575	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	12	Mile	Scoring Bituminous Pavement Surface
430B043	943	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	1,000	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	29	Acre	Mowing
656A010	5	Acre	Mulching
665J002	750	LF	Silt Fence
665O001	750	LF	Silt Fence Removal
665Q002	400	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 72,000.00)
701A227	12	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C002	8	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	89	Mile	Solid Temporary Traffic Stripe (Paint)
701G146	688	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	210	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	268	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	956	LF	Solid Traffic Stripe Removed (Tape)
701H007	210	LF	Broken Traffic Stripe Removed (Tape)
703A002	442	SQFT	Traffic Control Markings, Class 2, Type A
703D002	884	SQFT	Temporary Traffic Control Markings (Paint)
705A032	90	Each	Pavement Markers, Class A-H, Type 1-B
705A037	705	Each	Pavement Markers, Class A-H, Type 2-D

Item No.	Quantity	Units	Description
740B000	400	SQFT	Construction Signs
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car