

**Alabama Department of Transportation
Proposal Item Summary**

026. ACNU66421-ATRP(017)

JACKSON COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 6.00

for constructing the Planing, Resurfacing, and Traffic Stripe on East 2nd Street from the junction of SR-117 (Kentucky Avenue) to Patsy Lee Drive in Stevenson. Length 1.016 mi.

The Bracket Estimate on this project is from \$265,036 to \$323,933.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	1,625	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	16,257	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	1,585	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
610D003	640	SQYD	Filter Blanket, Geotextile
618C000	80	SQFT	Truncated Dome Retrofit
641S500	1	Each	Valve Box Reset
645K500	2	Each	Manhole Frame And Cover Reset
646J000	3	Each	Gas Valve Box Reset
650A000	340	CUYD	Topsoil
654A000	2,981	SQYD	Solid Sodding
665Q002	896	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 14,000.00)
701A231	3	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
703A002	783	SQFT	Traffic Control Markings, Class 2, Type A
703D001	783	SQFT	Temporary Traffic Control Markings
705A032	10	Each	Pavement Markers, Class A-H, Type 1-B
705A037	104	Each	Pavement Markers, Class A-H, Type 2-D
710A115	17	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710B021	26	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	610	SQFT	Construction Signs
740D000	30	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740F001	6	Each	Barricades, Type II
740I002	4	Each	Warning Lights, Type B
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car