

**Alabama Department of Transportation
Proposal Item Summary**

035. ERPR-9010(121)

COFFEE COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 4.00

for constructing the Bridge Replacement and Approaches on CR-215 at Shoal Creek east of the junction of CR-217 south of Jack. Length 0.086 mi.

The Bracket Estimate on this project is from \$282,746 to \$345,578.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D000	240	LF	Removing Pipe
210A000	442	CUYD	Unclassified Excavation
210D021	84	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	965	CUYD	Structure Excavation
214B001	139	CUYD	Foundation Backfill, Commercial
230A000	5	RBST	Roadbed Processing
301A025	1,289	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	1,186	SQYD	Bituminous Treatment A
424A340	110	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
502A001	17,211	LB	Steel Reinforcement (Grade 60)
524A011	166	CUYD	Culvert Concrete (Cast In Place)
600A000	1	LS	Mobilization
610C001	151	Ton	Loose Riprap, Class 2
610D003	493	SQYD	Filter Blanket, Geotextile
630A001	200	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	102	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
659C002	500	SQYD	Erosion Control Product, Type S2
665J002	310	LF	Silt Fence
665O001	310	LF	Silt Fence Removal
665Q002	160	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 12,600.00)
701A231	1	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	1	Mile	Solid Temporary Traffic Stripe
703A002	30	SQFT	Traffic Control Markings, Class 2, Type A
703D001	30	SQFT	Temporary Traffic Control Markings
740B000	304	SQFT	Construction Signs
740F002	10	Each	Barricades, Type III
740I002	5	Each	Warning Lights, Type B