

**Alabama Department of Transportation  
Proposal Item Summary**

**048. STPAA-HSIP-0189(503)**

**CRENSHAW COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-189 from the Coffee County Line to the junction of SR-9 (US-331) southeast of Brantley. Length 4.341 mi.

The Bracket Estimate on this project is from \$1,179,720 to \$1,441,880.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	37	SQYD	Removing Concrete Driveway
206D001	100	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
209A000	5	Each	Mailbox Reset, Single
210D021	1,079	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	459	STA	Machine Grading Shoulders
405A000	10,223	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	63,112	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410J000	1	Each	Smoothness Data Collection, Certified Inertial Profiler
424A341	6,102	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	78	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	2,050	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	2,612	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	9	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	325	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	3,057	CUYD	Topsoil
652A100	13	Acre	Seeding
652C000	30	Acre	Mowing
656A010	13	Acre	Mulching
659C002	630	SQYD	Erosion Control Product, Type S2
665A000	13	Acre	Temporary Seeding
665B001	39	Ton	Temporary Mulching
665E000	200	SQYD	Polyethylene
665G000	200	Each	Sand Bags
665J002	1,050	LF	Silt Fence
665O001	1,050	LF	Silt Fence Removal
665Q002	1,440	LF	Wattle
666A001	13	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 40,000.00)

Item No.	Quantity	Units	Description
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	36	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	180	SQFT	Traffic Control Markings, Class 2, Type A
703D001	180	SQFT	Temporary Traffic Control Markings
705A032	85	Each	Pavement Markers, Class A-H, Type 1-B
705A037	449	Each	Pavement Markers, Class A-H, Type 2-D
740B000	838	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car