

**Alabama Department of Transportation  
Proposal Item Summary**

---

**053. STPNU-1416(250)**

**CLAY COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on Blue Ridge Road from the junction of Clairmont Springs Road to the junction of Adams Gap Road. Length 1.150 mi.

The Bracket Estimate on this project is from \$207,438 to \$228,678.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
401B108	13,271	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	675	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	1,188	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	275	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	314	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,900.00)
701A231	3	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
703A002	68	SQFT	Traffic Control Markings, Class 2, Type A
705A032	14	Each	Pavement Markers, Class A-H, Type 1-B
705A037	138	Each	Pavement Markers, Class A-H, Type 2-D
740B000	195	SQFT	Construction Signs
740O000	1	Each	Pilot Car