

**Alabama Department of Transportation
Proposal Item Summary**

054. STPNU-6116(251)

TALLADEGA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-207 from the intersection of SR-34 to the junction of Hawthorne Hills Lane. Length 2.253 mi.

The Bracket Estimate on this project is from \$286,219 to \$349,824.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B108	26,102	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	793	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	2,684	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	580	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 15,400.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	7	Mile	Solid Temporary Traffic Stripe
701G252	225	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	184	SQFT	Traffic Control Markings, Class 2, Type A
705A032	48	Each	Pavement Markers, Class A-H, Type 1-B
705A037	264	Each	Pavement Markers, Class A-H, Type 2-D
740B000	353	SQFT	Construction Signs
740O000	1	Each	Pilot Car