

**Alabama Department of Transportation  
Proposal Item Summary**

---

**200. STPAA-NR13(939)**

**BALDWIN COUNTY**

Contract Time: 200 Working Days

for constructing the Curb Ramp Installations and Improvements at various locations on SR-3, SR-287, SR-16, SR-42, SR-59, SR-182, SR-161, and SR-104 as indicated in the plans.

The Bracket Estimate on this project is from \$303,311 to \$334,138.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$23.00 per set.

**THIS PROJECT HAS BEEN DESIGNATED AS AN SBE PROJECT, AND CAN ONLY BE BID ON BY QUALIFIED SBE CONTRACTORS THAT HAVE BEEN PRE-APPROVED BY THE ALDOT DBE UNIT AND ALDOT OFFICE ENGINEER.**

The Principal Items of work are approximately as follows

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
206C000	900	SQYD	Removing Concrete Sidewalk
206D003	126	LF	Removing Curb And Gutter
210D022	50	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0)
430B040	100	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
600A000	1	LS	Mobilization
618A000	1,320	SQYD	Concrete Sidewalk, 4" Thick
623C000	481	LF	Combination Curb & Gutter, Type C
650A000	250	CUYD	Topsoil
654A001	293	SQYD	Solid Sodding (Bermuda)
665E000	700	SQYD	Polyethylene
665G000	500	Each	Sand Bags
665Q002	500	LF	Wattle
674A000	11,000	LF	Construction Safety Fence
740B000	625	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit