

Alabama Department of Transportation
Proposal Item Summary

035. NH-0157(523)

MORGAN COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-157 from the Cullman County Line to the Lawrence County Line. Length 8.604 mi.

The Bracket Estimate on this project is from \$3,086,636 to \$3,772,555.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	40,264	Gal	Tack Coat
407B000	19	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	402,637	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	3,269	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A360	23,954	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	3,983	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	33	Mile	Scoring Bituminous Pavement Surface
430B047	2,564	Ton	Aggregate Surfacing (3/4" Down,Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 181,000.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	18	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	22,138	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	35	Mile	Broken Temporary Traffic Stripe
701C001	73	Mile	Solid Temporary Traffic Stripe
703A002	2,850	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,905	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,460	SQFT	Temporary Traffic Control Markings
705A030	1,140	Each	Pavement Markers, Class A-H, Type 2-C
705A032	140	Each	Pavement Markers, Class A-H, Type 1-B
705A038	70	Each	Pavement Markers, Class A-H, Type 2-E
740B000	4,213	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit