

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**038. NH-HSIP-0005(555)**

**WILCOX COUNTY**

Contract Time: 50 Working Days

DBE Goal Percent: 5.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-5 from the SR-28 Overpass to the north end of Chilatchee Creek Bridge to include the ramp to SR-28. Length 4.544 mi.

The Bracket Estimate on this project is from \$1,387,947 to \$1,696,379.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
209A000	2	Each	Mailbox Reset, Single
212A000	388	STA	Machine Grading Shoulders
401B108	71,522	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	4,453	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	83,619	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	8,235	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	576	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	2,100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	1,550	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	10	Mile	Scoring Bituminous Pavement Surface
430B043	300	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	300	CUYD	Topsoil
652A100	6	Acre	Seeding
652C000	32	Acre	Mowing
656A010	6	Acre	Mulching
665B001	18	Ton	Temporary Mulching
665J002	750	LF	Silt Fence
665O001	750	LF	Silt Fence Removal
665Q002	750	LF	Wattle
666A001	6	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,250	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C002	9	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	69	Mile	Solid Temporary Traffic Stripe (Paint)
701G146	2,016	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	767	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	482	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	2,498	LF	Solid Traffic Stripe Removed (Tape)

Item No.	Quantity	Units	Description
701H007	767	LF	Broken Traffic Stripe Removed (Tape)
703A002	4,900	SQFT	Traffic Control Markings, Class 2, Type A
703B002	192	SQFT	Traffic Control Legends, Class 2, Type A
703D002	5,637	SQFT	Temporary Traffic Control Markings (Paint)
703E002	72	SQFT	Temporary Traffic Control Legends (Paint)
705A030	460	Each	Pavement Markers, Class A-H, Type 2-C
705A032	660	Each	Pavement Markers, Class A-H, Type 1-B
705A037	535	Each	Pavement Markers, Class A-H, Type 2-D
705A038	295	Each	Pavement Markers, Class A-H, Type 2-E
740B000	896	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	3	Each	Portable Changeable Message Sign, Type 2