

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**011. ACBRZ63647-ATRP(004)**

**CALHOUN COUNTY**

Contract Time: 110 Working Days

DBE Goal Percent: 5.00

for constructing the Bridge Replacement on Rock Springs Road over an Unnamed Tributary to Ohatchee Creek. Length 0.312 mi.

The Bracket Estimate on this project is from \$995,010 to \$1,216,123.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 10+90.00
210A000	1,627	CUYD	Unclassified Excavation
210D001	1,734	CUYD	Borrow Excavation (Loose Truckbed Measurement)
230A000	16	RBST	Roadbed Processing
301A012	2,964	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,964	SQYD	Bituminous Treatment A
405A000	338	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	245	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	572	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	92	Ton	Aggregate Surfacing (1" Down, Crusher Run)
450B000	90	SQYD	Reinforced Cement Concrete Bridge End Slab
502A000	28,100	LB	Steel Reinforcement
502B000	1	LS	Steel Reinforcement For Bridge Superstructure, Station 10+55.00, Approximately 41,900 Pounds
506A004	58	LF	Drilled Shaft Excavation, 3'-0" Diameter
506A005	28	LF	Drilled Shaft Excavation, 3'-6" Diameter
506B001	50	LF	Special Drilled Shaft Excavation, 3'-0" Diameter
506B002	28	LF	Special Drilled Shaft Excavation, 3'-6" Diameter
506C040	108	LF	Drilled Shaft Construction, 3'-0" Diameter, Class DS1 Concrete
506C041	56	LF	Drilled Shaft Construction, 3'-6" Diameter, Class DS1 Concrete
506G000	2	Each	Crosshole Sonic Logging, 3'-0" Diameter
506G001	4	Each	Crosshole Sonic Logging, 3'-6" Diameter
508A000	4,360	LB	Structural Steel
510A007	83	CUYD	Bridge Substructure Concrete
510C051	1	LS	Bridge Concrete Superstructure, Station 10+55.00, Approximately 168 Cubic Yards
510E000	480	SQYD	Grooving Concrete Bridge Decks
511A051	24	Each	Elastomeric Bearing Type 2 (Mark B2)
513B004	704	LF	Pretensioned-Prestressed Concrete Girders, Type II (Specialty Item)
600A000	1	LS	Mobilization
602A000	15	Each	Right Of Way Markers
610C001	700	Ton	Loose Riprap, Class 2
610D003	717	SQYD	Filter Blanket, Geotextile
618B003	4	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
630C003	4	Each	Guardrail End Anchor, Type 13
630C070	4	Each	Guardrail End Anchor, Type 10 Series
650B000	630	CUYD	Topsoil From Stockpiles

Item No.	Quantity	Units	Description
652A100	2 Acre	Seeding	
656A010	2 Acre	Mulching	
665A000	2 Acre	Temporary Seeding	
665B001	6 Ton	Temporary Mulching	
665F000	200 Each	Hay Bales	
665J002	3,400 LF	Silt Fence	
665L000	200 LF	Floating Basin Boom	
665O001	3,400 LF	Silt Fence Removal	
665Q002	200 LF	Wattle	
666A001	2 Acre	Pest Control Treatment	
680A001	1 LS	Geometric Controls	
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 51,000.00)	
701A231	1 Mile	Solid White, Class 2, Type A Traffic Stripe	
701A235	1 Mile	Solid Yellow, Class 2, Type A Traffic Stripe	
701C001	1 Mile	Solid Temporary Traffic Stripe	
701G144	360 LF	Solid White, Class W, Type A Traffic Stripe	
701G152	360 LF	Solid Yellow, Class W, Type A Traffic Stripe	
705A037	43 Each	Pavement Markers, Class A-H, Type 2-D	
740B000	141 SQFT	Construction Signs	
740F002	8 Each	Barricades, Type III	
740I002	4 Each	Warning Lights, Type B	