

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**074. 99-402-690-000-802**

**LIMESTONE COUNTY**

Contract Time: 30 Working Days

for constructing the Resurfacing (Scrub Seal) and Traffic Stripe on the I-565 Service Roads from the Mooresville Road Interchange to the Beaverdam Creek Bridge. Length 3.256 mi.

The Bracket Estimate on this project is from \$360,370 to \$440,452.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206E043	441	Each	Removing Raised Pavement Markers
403B000	434	Ton	Micro-Surfacing Seal Coat, Type II
404G001	43,384	SQYD	Pavement Surfacing (Scrub Seal)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 21,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	395	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	9	Mile	Solid Temporary Traffic Stripe
701D008	10	Mile	Solid Traffic Stripe Removed (Plastic)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	1,853	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,853	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H011	395	LF	Dotted Traffic Stripe Removed (Plastic)
705A032	106	Each	Pavement Markers, Class A-H, Type 1-B
705A037	262	Each	Pavement Markers, Class A-H, Type 2-D
705A038	37	Each	Pavement Markers, Class A-H, Type 2-E
740B000	548	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
740O000	1	Each	Pilot Car