

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**033. FLAP-FLAP(014)**

**MONROE COUNTY**

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on Lock and Dam Road from the junction of Penn Road to the junction of Maiben Lake Road west of Wainwright. Length 1.729 mi.

The Bracket Estimate on this project is from \$436,801 to \$533,868.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	2,283	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	1,538	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	2,050	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	710	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	1,874	CUYD	Topsoil
652A100	3	Acre	Seeding
656A010	3	Acre	Mulching
665F000	25	Each	Hay Bales
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 24,300.00)
701A231	4	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	10	Mile	Solid Temporary Traffic Stripe
703A002	96	SQFT	Traffic Control Markings, Class 2, Type A
705A032	50	Each	Pavement Markers, Class A-H, Type 1-B
705A037	200	Each	Pavement Markers, Class A-H, Type 2-D
740B000	222	SQFT	Construction Signs
740O000	1	Each	Pilot Car