

Alabama Department of Transportation
Proposal Item Summary

039. PLH-6600(900)

WILCOX COUNTY

Contract Time: 45 Working Days

for constructing the Grading, Drainage, Pavement, and Traffic Stripe on CR-242 from the junction of CR-29 to a point approximately 0.328 mile east. Length 0.328 mi.

The Bracket Estimate on this project is from \$192,845 to \$235,699.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 3 Acres)
210A000	1,823 CUYD		Unclassified Excavation
230A000	18 RBST		Roadbed Processing
305B071	200 Ton		Coarse Aggregate, Section 801, For Miscellaneous Use
305B078	200 Ton		Crushed Aggregate, Section 825, Type B, For Miscellaneous Use
401A000	4,296 SQYD		Bituminous Treatment A
405A000	260 Gal		Tack Coat
407B000	1 Mile		Joint Sealant For Hot Mix Asphalt Pavement
424A340	295 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	473 Ton		Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
535A080	107 LF		18" Side Drain Pipe (Class 3 R.C.)
600A000	1 LS		Mobilization
602A000	18 Each		Right Of Way Markers
610D003	414 SQYD		Filter Blanket, Geotextile
619A101	4 Each		18" Side Drain Pipe End Treatment, Class 1
637A000	21 LF		Fence Reset
650A000	478 CUYD		Topsoil
652A100	1 Acre		Seeding
654A000	24 SQYD		Solid Sodding
656A010	1 Acre		Mulching
665A000	1 Acre		Temporary Seeding
665B001	3 Ton		Temporary Mulching
665I000	80 Ton		Temporary Riprap, Class 2
665J002	400 LF		Silt Fence
665O001	400 LF		Silt Fence Removal
665Q002	250 LF		Wattle
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 17,300.00)
701A227	1 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	48 SQFT		Traffic Control Markings, Class 2, Type A
710A126	8 SQFT		Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B001	13 LF		Roadway Sign Post (#3 "U" Channel Galvanized Steel)
740B000	54 SQFT		Construction Signs
740D000	18 Each		Channelizing Drums
740F002	4 Each		Barricades, Type III
740I002	2 Each		Warning Lights, Type B