

Alabama Department of Transportation
Proposal Item Summary

042. STPAA-5118(250)

MONTGOMERY COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 4.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-54 (Old Selma Road) from the Lowndes County Line to the Montgomery City Limits. Length 3.782 mi.

The Bracket Estimate on this project is from \$902,308 to \$1,102,821.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	137	SQYD	Removing Concrete Driveway
206D001	1,148	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
206E019	4	Each	Removing Guardrail End Anchor (Type 10)
305B071	32	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
405A000	6,659	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	945	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A366	6,959	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	2,931	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A004	1,004	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
652A100	6	Acre	Seeding
656A010	6	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 48,400.00)
701A231	8	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	6	Mile	Broken Temporary Traffic Stripe
701C001	10	Mile	Solid Temporary Traffic Stripe
703A002	330	SQFT	Traffic Control Markings, Class 2, Type A
705A032	110	Each	Pavement Markers, Class A-H, Type 1-B
705A037	375	Each	Pavement Markers, Class A-H, Type 2-D
740B000	402	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car