

Alabama Department of Transportation
Proposal Item Summary

051. STPNU-1417(251)

CLAY COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-47 (State Lake Road) from the intersection of SR-49 to the junction of SR-9 in Delta. Length 6.942 mi.

The Bracket Estimate on this project is from \$966,484 to \$1,181,259.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	17	SQYD	Removing Concrete Driveway
401B108	81,233	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	8,146	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	7,150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	275	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	325	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	1,426	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,184	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 59,000.00)
701A231	14	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	26	Mile	Solid Temporary Traffic Stripe
703A002	352	SQFT	Traffic Control Markings, Class 2, Type A
705A032	79	Each	Pavement Markers, Class A-H, Type 1-B
705A037	838	Each	Pavement Markers, Class A-H, Type 2-D
740B000	326	SQFT	Construction Signs
740O000	1	Each	Pilot Car