

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**054. STPNU-2418(250)**

**DALLAS COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 7.00

for constructing the Resurfacing and Traffic Stripe on CR-33 from the Five Points Intersection with CR-31 to the junction of CR-955. Length 1.059 mi.

The Bracket Estimate on this project is from \$179,593 to \$219,502.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
401B108	11,186	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	1,455	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	1,196	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	260	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	167	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	208	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665F000	60	Each	Hay Bales
665J002	300	LF	Silt Fence
665O001	300	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,000.00)
701A235	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C002	1	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	5	Mile	Solid Temporary Traffic Stripe (Paint)
701G251	225	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	20	SQFT	Traffic Control Markings, Class 2, Type A
703D002	40	SQFT	Temporary Traffic Control Markings (Paint)
705A032	35	Each	Pavement Markers, Class A-H, Type 1-B
705A037	105	Each	Pavement Markers, Class A-H, Type 2-D
740B000	231	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car