

**Alabama Department of Transportation
Proposal Item Summary**

069. 99-402-690-000-803

COLBERT, LAWRENCE, AND MORGAN COUNTIES

Contract Time: 35 Working Days

for constructing the Resurfacing (Micro-Surfacing Seal Coat) and Traffic Stripe on SR-67 from MP 19.600 to MP 24.000 (Site 1); on SR-33 from MP 17.400 to MP 19.700 (Site 2); and on SR-247 from MP 19.000 to 20.800 (Site 3). Length 8.499 mi.

The Bracket Estimate on this project is from \$475,489 to \$581,154.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E043	540	Each	Removing Raised Pavement Markers
403B000	1,197	Ton	Micro-Surfacing Seal Coat, Type II
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 27,000.00)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	9	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	425	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	17	Mile	Broken Temporary Traffic Stripe
701C001	51	Mile	Solid Temporary Traffic Stripe
701D008	21	Mile	Solid Traffic Stripe Removed (Plastic)
701D015	9	Mile	Broken Traffic Stripe Removed (Plastic)
701H011	425	LF	Dotted Traffic Stripe Removed (Plastic)
703A002	50	SQFT	Traffic Control Markings, Class 2, Type A
703C001	50	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	100	SQFT	Temporary Traffic Control Markings
705A032	630	Each	Pavement Markers, Class A-H, Type 1-B
705A037	850	Each	Pavement Markers, Class A-H, Type 2-D
705A038	230	Each	Pavement Markers, Class A-H, Type 2-E
740B000	302	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car